

**CORRIGENDUM # 1****TENDER FOR LAYING OF MDPE NETWORK, GI/CU/MLC INSTALLATION AND MRS FABRICATION IN NCT OF DELHI, UP, HARYANA & RAJASTHAN****TENDER DOCUMENT NO. IGL/ET2/CP/CP18519, Dated: 17.07.2025****VCS REF. NO.VCS/NOIDA/C&P/18519/WC/MDPE/01****Owner - Indraprastha Gas Ltd.****Consultant - VCS Quality Services Pvt. Ltd.****Date: 02.08.2025**

Sl. No.	TenderPage No	Tender / Cl. No.	Description	Amendment/ Addition/ Modification/ Deletion	
1	Page No. 133, 153,170, 189, 208, 227 of 244	SOR_ Segment-1,2,3,4,5 & 6 & Attachment-1,2,3,4,5 & 6 of Commercial Volume I of II	All service lines left out initially during mainline laying, shall be laid under above mentioned SOR within six months of gas charging of a particular area by the same contractor. In Open trench method/ moiling, no extra rate shall be payable for casing installation. Roads, Pavement, Footpaths, Kutcha etc. shall be made motorable once the pipeline is laid. Liasoning and HSE shall not be paid wrt this SOR	Deletion	Below paragraph is being deleted from All Segments i.e. Segment-1,2,3,4,5 & 6 Attachment-1: Estimated Cost for Segment-1,2,3,4,5 & 6 "All service lines left out initially during mainline laying, shall be laid under above mentioned SOR within six months of gas charging of a particular area by the same contractor. In Open trench method/ moiling, no extra rate shall be payable for casing installation. Roads, Pavement, Footpaths, Kutcha etc. shall be made motorable once the pipeline is laid. Liasoning and HSE shall not be paid wrt this SOR". Note: The aforementioned paragraph in SOR Segment-1,2,3,4,5 & 6 is no longer considered a part of it. Bidders are advised to quote accordingly.
2	Page No. 39 of 404	Clause No. 14.5 of Technical Volume II of II	Clause No. 14.5: LAYING OF SERVICE LINE IN OLD PROJECT AND O&M AREA:	Amendment	Clause 14.5 of Technical Volume has been amended. Refer attached Annexure - 1

Note: All other Terms & Conditions of the Tender Document remain unchanged

Clause No. 14.5 has been amended in Technical Volume:

14.5 LAYING OF SERVICE LINE IN OLD PROJECT AND O&M AREA:

O&M area shall be defined as those areas where PE line is already charged and handed over to owner. However, Old Project area shall be defined as an area where MDPE line is already been laid by another contractor (currently not working in respective zone), only service line connectivity shall be done by the contractor. Laying of pipeline (for 20 & 32mm) in all type of surface i.e. all kinds including Kutcha, metal, concrete (PCC/RCC), bituminous, tiled, brick lined etc. after racking up of hard surface of any type by any methodology. Roads, Pavement, Footpaths etc. shall be made motor able once the pipeline is laid. Supply & installation of GI Sleeve / Half round Concrete sleeve shall be included in laying rates. The rate includes liasoning with statutory bodies and no separate rates are payable. Wherever service lines are to be laid after dismantling nallah / drain, no additional cost for dismantling and repairing shall be payable.

All service lines left out initially during mainline laying and laid by other contractor after gas charging shall be paid as per SOR 4.

Construction of RCC structure for MDPE protection for drain/nallah crossing as per Dwg.- 15792-10-03-46A; payment against such executed item shall be payable as per SOR item no. 4.5. Construction of this structure shall be as per instruction of Site In-charge & in locations which are not prone to damage by heavy vehicular movement (Rates shall be irrespective of drain width).